

EXPLOSION DE INSUMOS

Descripción	Unidad	P.Unitario	Cantidad	Parcial	ABC
MATERIALES				28,909.03	44.1%
HORMIGON ELABORADO H21 CANTO R	M3	100.00	173.000	17,300.00	26.4%
HIERRO REDONDO ESTRIADO 42/U50	TON	496.00	18.024	8,939.90	13.6%
ALAMBRE Ac.RECOCI.(NEGRO)(1.63	KILO	0.97	131.558	127.61	0.2%
ALAMBRE Ac.RECOCI.(NEGRO)(4.06	KILO	0.90	93.946	84.55	0.1%
CLAVO ACERO DULCE PUNTA PARIS(PAQ	1.34	118.302	158.53	0.2%
MADERA PINO SALIGNA EN BRUTO	M3	136.00	16.900	2,298.44	3.5%
EQUIPOS				249.26	0.4%
MULTIFUNCION [56 HP]	HORA	9.30	2.483	23.09	0.0%
GUINCHE A ENGRANAJES(8 HP)	HORA	1.13	5.360	6.06	0.0%
VIBRADOR[2 HP]	HORA	0.38	6.920	2.63	0.0%
CAMION VOLCADOR(6M3)120 HP	HORA	13.32	14.014	186.67	0.3%
SIERRA CIRCULAR [1.8KW]	HORA	0.24	128.401	30.82	0.0%
MANO DE OBRA DIRECTA				33,506.15	51.2%
OFICIAL ENCOFRADOR	HORA	5.20	2632.320	13,688.59	20.9%
OFICIAL ARMADOR	HORA	5.20	749.749	3,898.84	6.0%
OFICIAL HORMIGON	HORA	4.37	103.965	453.87	0.7%
OFICIAL MAQUINISTA ESPECIALIZA	HORA	5.20	16.497	85.79	0.1%
OFICIAL MAQUINISTA	HORA	4.37	4.556	19.89	0.0%
AYUDANTE ENCOFRADOR	HORA	3.72	2718.987	10,124.42	15.5%
AYUDANTE ARMADOR	HORA	3.72	860.302	3,203.42	4.9%
AYUDANTE HORMIGON	HORA	3.72	339.718	1,264.97	1.9%
AYUDANTE EXCAVACION	HORA	3.63	91.219	330.88	0.5%
PEON	HORA	3.08	141.316	435.48	0.7%
SUBCONTRATOS				2,830.90	4.3%
BOMBA HORMIGON TRASLADO	VEZ	500.00	3.932	1,965.90	3.0%
BOMBA HORMIGON SERVICIO	M3	5.00	173.000	865.00	1.3%
TOTAL				65,495.34	100.0%